



# Water, Wastewater and Reclaimed Water Technical Specifications

October 2023



## PREFACE


The enclosed Technical Specifications have been prepared to provide engineering and construction data and recommendations applicable to the design and construction of water, wastewater, and reclaimed water utilities designed and constructed with the intent of ultimate ownership being conveyed to Hillsborough County Public Utilities Water Resources Department.

The misuse or misapplication of data contained in this document could result in system failures, severe damage to other property, or serious injury to persons. Hillsborough County does not assume any liability for any losses or damages resulting from the use or application of the materials and data set forth in these technical specifications. The Professional Engineer of Record will be responsible for the specific project specifications under his or her control as set forth under Chapter 471 F.S., et al. and will be required to submit signed, dated, and sealed specifications for his or her design project(s) as set forth in his or her contract.

To facilitate review of the designer's project documents, the basic Technical Specifications documents must not be modified by the designer. Any proposed exceptions to the basic Technical Specifications must be listed and attached to the front of the Technical Specifications under a section entitled "Special Conditions".

These standards apply to Hillsborough County Public Utilities Water Resources Department facilities. Refer the appropriate section of the Hillsborough County Public Works Standard Specifications for Construction, latest version, for all work outside the scope of specifications attached hereto.

As material specifications, technical criteria and County polices change to meet new needs and changing technology, it will become necessary to revise and update this manual. The County's procedure for making revisions which includes issuing technical bulletins, accepting public comments, and requesting design exceptions can be previewed on the County's website at [www.hillsboroughcounty.org](http://www.hillsboroughcounty.org). In addition, you can submit comments and suggestions for changes to the manual using the online "Comment on PUD / PW Technical Publications" form located on the County's website.

APPROVED:   
Lisa R. Rhea, PE  
Director, Water Resources Department

10/25/2023

Date

**OCTOBER 31, 2023**

Effective Date



# Accommodation Statement

In accordance with the requirements of title II of the Americans with Disabilities Act of 1990 ("ADA"), Hillsborough County will not discriminate against qualified individuals with disabilities on the basis of disability in its services, programs, or activities. Persons with disabilities who need an accommodation for this document should contact the Hillsborough County ADA Officer at (813) 276-8401; TTY: 7-1-1.



## TABLE OF CONTENTS

### DIVISION 03 – CONCRETE

<b>SPECIFICATION 031000: FORMS AND FORMWORK</b>	<b>1</b>
<b>PART 1.0 GENERAL</b>	<b>1</b>
1.1 Description	1
1.2 Reference Documents	1
1.3 Submittals	1
1.4 Related Work	1
<b>PART 2.0 PRODUCT</b>	<b>2</b>
2.1 Quality Assurance	2
2.2 Forms and Accessories	2
2.3 Product Delivery, Storage, and Handling	3
<b>PART 3.0 EXECUTION</b>	<b>3</b>
3.1 Fabrication	3
3.2 Preparation	3
3.3 Installation, Removal, and Shoring	3
3.4 Embedded Items	4
3.5 Field Quality Control	5
3.6 Joints	5
3.7 Removal of Forms, False Work, and Centering	5
<b>SPECIFICATION 032000: CONCRETE REINFORCEMENT</b>	<b>1</b>
<b>PART 1.0 GENERAL</b>	<b>1</b>
1.1 Description	1
1.2 Reference Documents	1
1.3 Shop Drawings and Submittals	1
1.4 Related Work	1
<b>PART 2.0 PRODUCT</b>	<b>2</b>
2.1 General	2
2.2 Quality Assurance	2
2.3 Material	2
2.4 Product Delivery, Storage, and Handling	3
<b>PART 3.0 EXECUTION</b>	<b>3</b>
3.1 Cutting and Bending – Reinforcement	3
3.2 Bar Supports and Spacers	3
3.3 Steel Reinforcement	4
3.4 Splicing	4
3.5 Concrete Protection for Reinforcement	4



3.6	Field Quality Control .....	5
<b>SPECIFICATION 033000: CAST-IN-PLACE CONCRETE.....</b>		<b>1</b>
<b>PART 1.0</b>	<b>GENERAL.....</b>	<b>1</b>
1.1	Description.....	1
1.2	Reference Documents .....	1
1.3	Submittals .....	1
1.4	Related Work .....	2
<b>PART 2.0</b>	<b>PRODUCT .....</b>	<b>2</b>
2.1	Quality Assurance.....	2
2.2	Materials .....	3
2.3	Product Delivery, Storage, and Handling .....	6
<b>PART 3.0</b>	<b>EXECUTION.....</b>	<b>7</b>
3.1	Field Quality Control .....	7
3.2	Material Preparation.....	9
3.3	Conveying.....	11
3.4	Preparation for Placement.....	12
3.5	Placement.....	12
3.6	Curing and Protecting .....	14
3.7	Weather Protection.....	15
3.8	Defective Concrete.....	15
3.9	Damaged Work .....	15
3.10	Tolerance for Concrete Construction.....	16

## DIVISION 33 – UTILITIES

<b>SPECIFICATION 330523: HORIZONTAL DIRECTIONAL DRILLING .....</b>		<b>1</b>
<b>PART 1.0</b>	<b>GENERAL.....</b>	<b>1</b>
1.1	Description.....	1
1.2	Reference Documents .....	1
1.3	Related Work .....	1
1.4	Warranty .....	1
1.5	Submittals .....	2
<b>PART 2.0</b>	<b>PRODUCTS .....</b>	<b>2</b>
2.1	General.....	2
2.2	Polyvinyl Chloride Pipe and Couplings (PVC) .....	3
2.3	Ductile Iron Pipe and Fittings.....	4
<b>PART 3.0</b>	<b>EXECUTION/INSTALLATION.....</b>	<b>4</b>
3.1	Description.....	4
3.2	Installation .....	5



<b>SPECIFICATION 330524: BORING AND JACKING .....</b>	<b>1</b>
<b>PART 1.0 GENERAL.....</b>	<b>1</b>
1.1 Description.....	1
1.2 Reference Documents.....	1
1.3 Shop Drawings and Submittals.....	1
1.4 Related Work.....	2
<b>PART 2.0 PRODUCT .....</b>	<b>3</b>
2.1 Pipe Casing.....	3
2.2 Carrier Pipe.....	3
2.3 Auguring Fluids.....	3
<b>PART 3.0 EXECUTION.....</b>	<b>3</b>
3.1 General.....	3
3.2 Excavation.....	4
3.3 Boring and Jacking.....	4
3.4 Grouting.....	4
3.5 Loss of Ground.....	4
3.6 Tolerances.....	5
3.7 Responsibility.....	5
3.8 Installation of Pipe.....	5
3.9 Insurance Requirements and Fees.....	5
3.10 Successful Completion.....	6
 <b>SPECIFICATION 331001: WATER MAINS AND APPURTENANCES .....</b>	 <b>1</b>
<b>PART 1.0 GENERAL.....</b>	<b>1</b>
1.1 Description.....	1
1.2 Reference Documents.....	1
1.3 Shop Drawings and Submittals.....	2
1.4 Related Work.....	2
<b>PART 2.0 DESIGN.....</b>	<b>3</b>
2.1 Line Sizing Criteria.....	3
2.2 Line Routing.....	3
2.3 Depth of Cover.....	4
2.4 Protection of Potable Water Systems.....	4
2.5 Cross-Connection Control.....	5
2.6 Meters and Metering Assemblies.....	6
2.7 Service Connections.....	7
2.8 Fire Hydrant Spacing, Location, and Flow.....	8
2.9 System Valves and Valve Location.....	9
2.10 Pipe, Fittings, and Appurtenances.....	10
2.11 Dedicated Sampling Taps.....	12
<b>PART 3.0 PRODUCTS.....</b>	<b>12</b>
3.1 Pipe Material.....	12



3.2	Ductile Iron Pipe and Fittings .....	13
3.3	Polyvinyl Chloride Pipe and Fittings .....	14
3.4	Gaskets .....	15
3.5	Polyethylene (HDPE) Service Pipe and Tubing .....	15
3.6	Valves and Appurtenances .....	16
3.7	Meters and Meter Boxes .....	19
3.8	Fire Hydrants .....	20
3.9	Backflow Preventers .....	21
3.10	Auto-Flushers .....	22
<b>PART 4.0</b>	<b>CONSTRUCTION .....</b>	<b>24</b>
4.1	Work at Highway or Railroad Crossings .....	24
4.2	Preconstruction Pipe Inspection/Certification .....	24
4.3	Installation .....	24
4.4	Trench Excavation .....	26
4.5	Handling and Cutting Pipe .....	27
4.6	Fusion Process .....	27
4.7	Pipe Laying .....	28
4.8	Installing Joints .....	28
4.9	Installing Appurtenances .....	29
4.10	Water Service Connections .....	32
4.11	Polyethylene Tube Encasement/Polywrap .....	32
4.12	Backfill/Compaction .....	33
4.13	Temporary Water Service for Construction .....	35
4.14	Flushing and Cleaning .....	36
4.15	Hydrostatic Testing .....	37
4.16	Disinfecting Water Systems .....	37
4.17	Connection to Existing Water Mains .....	38
<b>PART 5.0</b>	<b>PRESSURE TESTING FORMS .....</b>	<b>40</b>
	<b>SPECIFICATION 331002: WATER EXHIBITS .....</b>	<b>1</b>
	<b>SPECIFICATION 333001: GRAVITY WASTEWATER SEWERS AND APPURTENANCES .....</b>	<b>1</b>
<b>PART 1.0</b>	<b>GENERAL .....</b>	<b>1</b>
1.1	Description .....	1
1.2	Reference Documents .....	1
1.3	Shop Drawings and Submittals .....	1
1.4	Related Work .....	2
<b>PART 2.0</b>	<b>DESIGN .....</b>	<b>2</b>
2.1	Flow Criteria .....	2
2.2	Minimum Line Size .....	2
2.3	Alignment .....	2
2.4	Depth of Cover .....	3



2.5	Slope .....	3
2.6	Horizontal Separation .....	3
2.7	Crossings.....	3
2.8	Gravity Laterals .....	4
2.9	Wastewater Manholes.....	4
2.10	Manhole Frames and Covers .....	5
2.11	Waterproof and Protective Coatings .....	6
<b>PART 3.0</b>	<b>PRODUCTS .....</b>	<b>6</b>
3.1	Material.....	6
3.2	PVC Pipe and Fittings.....	6
3.3	Manholes.....	7
3.4	Manhole Frames and Covers .....	8
3.5	Waterproof and Protective Coatings.....	9
<b>PART 4.0</b>	<b>CONSTRUCTION.....</b>	<b>9</b>
4.1	Work at Highway or Railroad Crossings .....	9
4.2	Preconstruction Pipe Inspection/Certification .....	9
4.3	Installation .....	9
4.4	Trench Excavation .....	10
4.5	Handling and Cutting Pipe.....	11
4.6	Pipe Laying.....	11
4.7	Installing Joints.....	12
4.8	Installing Manholes.....	12
4.9	Gravity Laterals .....	13
4.10	Backfill/Compaction.....	13
4.11	Connections to Gravity Systems.....	15
4.12	Taking Existing Wastewater Systems Out of Service.....	16
4.13	Inspection and Testing .....	16
<b>PART 5.0</b>	<b>TELEVISIONING OF LINES .....</b>	<b>20</b>
5.1	Procedures for Televisioning Sanitary Sewer Mains .....	20
<b>SPECIFICATION 333002: WASTEWATER FORCE MAINS AND APPURTENANCES .....</b>		<b>1</b>
<b>PART 1.0</b>	<b>GENERAL.....</b>	<b>1</b>
1.1	Description.....	1
1.2	Reference Documents .....	1
1.3	Shop Drawings and Submittals.....	1
1.4	Related Work .....	2
<b>PART 2.0</b>	<b>DESIGN.....</b>	<b>2</b>
2.1	Flow Criteria .....	2
2.2	Minimum Size.....	3
2.3	Line Routing .....	3
2.4	Depth of Cover.....	4





2.5	Horizontal Separation .....	4
2.6	Vertical Crossings .....	4
2.7	System Valves and Valve Location .....	4
2.8	Pipe, Fittings, and Appurtenances .....	5
2.9	Connections to County Systems .....	6
<b>PART 3.0</b>	<b>PRODUCTS .....</b>	<b>6</b>
3.1	Material .....	6
3.2	Polyvinyl Chloride Pipe and Fittings .....	6
3.3	Ductile Iron Pipe and Fittings .....	7
3.4	Gaskets .....	9
3.5	Valves and Appurtenances .....	9
<b>PART 4.0</b>	<b>CONSTRUCTION .....</b>	<b>11</b>
4.1	Work at Highway or Railroad Crossings .....	11
4.2	Preconstruction Pipe Inspection/Certification .....	11
4.3	Installation .....	12
4.4	Trench Excavation .....	14
4.5	Handling and Cutting Pipe .....	14
4.6	Fusion Process .....	15
4.7	Pipe Laying .....	15
4.8	Installing Joints .....	16
4.9	Installing Appurtenances .....	17
4.10	Polyethylene Tube Encasement/Polywrap .....	18
4.11	Backfill/Compaction .....	19
4.12	Flushing and Cleaning .....	20
4.13	Hydrostatic Testing .....	21
4.14	Connections to Existing System .....	22
<b>PART 5.0</b>	<b>PRESSURE TESTING FORMS .....</b>	<b>24</b>
	<b>SPECIFICATION 333003: WASTEWATER PUMPING STATION .....</b>	<b>1</b>
<b>PART 1.0</b>	<b>GENERAL .....</b>	<b>1</b>
1.1	Description .....	1
1.2	Reference Documents .....	2
1.3	Shop Drawings and Submittals .....	3
1.4	Tools and Spare Parts .....	3
1.5	As Built/Record Drawings & Asset Data Spreadsheets .....	4
1.6	Related Work .....	4
<b>PART 2.0</b>	<b>DESIGN AND CONSTRUCTION STANDARDS .....</b>	<b>5</b>
2.1	Siting Requirements .....	5
2.2	Horizontal Separation .....	6
2.3	Crossings .....	6
2.4	Flow .....	6
2.5	Total Dynamic Head (TDH) .....	6



2.6	System Head versus Pump Capacity Analysis.....	7
2.7	Electrical Classification .....	7
2.8	Pumps.....	7
2.9	Wet Wells .....	8
2.10	Piping Design.....	9
2.11	Station Access.....	9
2.12	Main Disconnect .....	9
2.13	Phase Protection .....	10
2.14	In-Fill Pump Stations .....	10
<b>PART 3.0</b>	<b>PRODUCTS .....</b>	<b>11</b>
3.1	Wet Well.....	11
3.2	Discharge Piping and Appurtenances .....	12
3.3	Wastewater Pumps.....	15
3.4	Potable Water Services .....	16
3.5	Pumping Station Controls .....	17
3.6	Remote Telemetry and Appurtenances.....	19
3.7	Conduit Systems .....	23
3.8	Wiring Systems.....	23
3.9	Pump Discharge Taps and Pressure Measuring Systems.....	24
3.10	Level Measuring System.....	25
<b>PART 4.0</b>	<b>CONSTRUCTION.....</b>	<b>25</b>
4.1	Site Work .....	25
4.2	Wet Wells .....	26
4.3	Piping and Equipment.....	26
4.4	Electrical .....	27
4.5	Control/RTU Cabinets and Appurtenances.....	29
4.6	Site Paving and Fencing.....	30
4.7	Final Inspection and Testing.....	32
<b>PART 5.0</b>	<b>WASTEWATER PUMPING STATION CONSTRUCTION START-UP PROCEDURE.....</b>	<b>36</b>
5.1	Project Substantially Completed.....	36
5.2	Pump Station Start-up Checklist.....	36
	<b>SPECIFICATION 333006: SEWER EXHIBITS .....</b>	<b>1</b>
	<b>SPECIFICATION 339001: RECLAIMED WATER MAINS AND APPURTENANCES.....</b>	<b>1</b>
<b>PART 1.0</b>	<b>GENERAL.....</b>	<b>1</b>
1.1	Description.....	1
1.2	Reference Documents .....	1
1.3	Shop Drawings and Submittals.....	2
1.4	Related Work .....	2
<b>PART 2.0</b>	<b>DESIGN.....</b>	<b>3</b>



2.1	Line Sizing Criteria.....	3
2.2	Line Routing .....	3
2.3	Depth of Cover.....	4
2.4	Separation of Reclaimed Water, Potable Water, & Sewer Lines.....	4
2.5	Cross-Connection Control .....	5
2.6	Golf Courses and Other Major Users.....	5
2.7	Meters and Metering Assemblies.....	6
2.8	Service Connections.....	8
2.9	System Valves and Valve Location .....	8
2.10	Pipe, Fittings, and Appurtenances.....	9
2.11	System Identification and Signage.....	11
2.12	Hose Bibb Assembly.....	11
<b>PART 3.0</b>	<b>PRODUCTS .....</b>	<b>12</b>
3.1	Pipe Material.....	12
3.2	Ductile Iron Pipe and Fittings .....	12
3.3	Polyvinyl Chloride Pipe and Fittings.....	14
3.4	Gaskets.....	15
3.5	Polyethylene (HDPE) Service Pipe and Tubing .....	15
3.6	Valves and Appurtenances.....	15
3.7	Meter and Meter Boxes.....	19
3.8	Hose Bibb Assembly.....	20
<b>PART 4.0</b>	<b>CONSTRUCTION.....</b>	<b>21</b>
4.1	Work at Highway or Railroad Crossings .....	21
4.2	Preconstruction Pipe Inspection/Certification .....	21
4.3	Installation .....	21
4.4	Trench Excavation .....	23
4.5	Handling and Cutting Pipe.....	23
4.6	Fusion Process .....	24
4.7	Pipe Laying .....	24
4.8	Installing Joints .....	25
4.9	Installing Appurtenances .....	26
4.10	Golf Courses and Other Major Users.....	27
4.11	Service Connections.....	28
4.12	Installing Back-Flow Prevention Devices.....	28
4.13	Hose Bibb Connection Assembly .....	28
4.14	Polyethylene Tube Encasement/Polywrap.....	29
4.15	Backfill/Compaction.....	30
4.16	Temporary Potable Water Service for Construction.....	31
4.17	Flushing and Cleaning .....	31
4.18	Hydrostatic Test.....	32
4.19	Connection to Existing Reclaimed Water Mains.....	33
<b>PART 5.0</b>	<b>PIPE SIZING CRITERIA.....</b>	<b>35</b>
5.1	Design Standard for Reclaimed Water Distribution Systems .....	35
5.2	Residential Subdivisions.....	35
5.3	Commercial Developments.....	36



**PART 6.0 PRESSURE TESTING FORMS .....37**  
**SPECIFICATION 339002: RECLAIMED WATER EXHIBITS.....1**

## **APPENDICES**

**APPENDIX A: STANDARD ABBREVIATIONS**

**APPENDIX B: APPROVED PRODUCTS AND MATERIALS**

**APPENDIX C: PROCEDURES FOR WATER MAIN CLEANING,  
DISINFECTION, AND BACTERIOLOGICAL TESTING**

**APPENDIX D: PUMP STATION CONTROL AND SCADA  
REQUIREMENTS**